GOVERNMENT OF TAMIL NADU
PUBLIC WORKS DEPARTMENT

OFFICE OF THE ENGINEER-IN-CHIEF, CHIEF ENGINEER (GENERAL) & CHIEF ENGINEER, CHENNAI REGION, PWD, CHENNAI-5.

Present: ***Er. R. Viswanath, M.E. (Structures),***
Engineer-in-Chief, Chief Engineer (General) &
Chief Engineer, Chennai Region, PWD,
Chepauk, Chennai-5.

Proceedings No. HDO (B) / 65325 / 2001, dated 11.08.2022

Sub: Buildings – Common Schedule of Plinth Area Rates for the Valuation of Buildings for Rental Calculation Purpose by Public Works Department and for the purpose of Collection of Stamp Duty by Registration Department – **Approved for the year 2022-2023 for adoption with effect from 16.08.2022** – Communication of – Regarding.

Ref: This office Proc. No.HDO (B) / 65325 / 2001, dated 14.09.2021.

The common Schedule of Plinth Area Rates for the Valuation of Buildings (i) for Rental Calculation Purpose by PWD and (ii) for Collection of Stamp Duty by Registration Department during the year **2022-2023** is hereby approved and enclosed vide Annexure-I for adoption with effect from **16.08.2022**. The approved rates shall be in operation for **One Year (i.e.) upto 15.08.2023.**

The Chief Engineers, the Superintending Engineers and the Executive Engineers of Public Works Department are requested to adopt the above rates for working out the rental calculation of buildings.

The receipt of this proceeding together with Annexure-I shall be acknowledged.

Encl.: Annexure-I

for Engineer-in-Chief,
Chief Engineer (General) &
Chief Engineer, Chennai Region, PWD.

12/8/2022

To

The Chief Engineer (Buildings), PWD, Trichy Region, Trichy.
The Chief Engineer (Buildings), PWD, Madurai Region, Madurai.
The Chief Engineer (Buildings), PWD, Coimbatore Region, Coimbatore.

Verified © RealState™

Copy with Annexure-I communicated to:

All the Superintending Engineers of Public Works Department.

All the Executive Engineers of Public Works Department.

The Senior Audit Officer, Indian Audit and Accounts Department, O/o. the Accountant General (Audit-II), Tamil Nadu & Puduchery, Lekhapariksha Bhavan, No.361, Anna Salai, Teynampet, Chennai-18.

The Inspector General of Registration, No.100, Santhome High Road, Chennai-28.

The Joint Chief Engineer (Buildings), PWD, Chennai-5.

The Joint Chief Engineer (Electrical), PWD, Chennai-5.

The Deputy Chief Engineer (Buildings), PWD, Chennai-5.

The Head Draughting Officer, Office of the EIC, CE (GL) & CE, CR, PWD, Chennai-5.

All the Assistant Executive Engineers of all Technical Sections of Office of the EIC, CE (GL) & CE, CR, PWD, Chennai-5.

Copy to File / Spare copy.

Verified RealEstate

OFFICE OF THE ENGINEER-IN-CHIEF, CHIEF ENGINEER (GENERAL) & CHIEF ENGINEER, CHENNAI REGION, PWD, CHEPAUK, CHENNAI-5

COMMON SCHEDULE OF PLINTH AREA RATES FOR THE VALUATION OF BUILDINGS FOR RENTAL CALCULATION PURPOSE BY PWD AND FOR THE PURPOSE OF COLLECTION OF STAMP DUTY BY REGISTRATION DEPARTMENT DURING THE YEAR 2022-2023 [WITH EFFECT FROM 16.08.2022]

INDEX

Sl. No.	Description	Page No.
	GENERAL NOTE	1
I	CLASS-A (LOAD BEARING STRUCTURE)	2 & 3
II	CLASS-A1 (LOAD BEARING STRUCTURE)	4 & 5
III	CLASS-B (LOAD BEARING STRUCTURE)	6 & 7
IV	CLASS-B1 (LOAD BEARING STRUCTURE)	8 & 9
V	CLASS-C (LOAD BEARING STRUCTURE)	10
VI	CLASS-D (LOAD BEARING STRUCTURE)	11 & 12
VII	CLASS-D1 (LOAD BEARING STRUCTURE)	13 & 14
VIII	CLASS-E (RCC FRAMED STRUCTURE)	15
IX	CLASS-E1 (RCC FRAMED STRUCTURE)	16
X	CLASS-E2 (RCC FRAMED STRUCTURE)	17
XI	CLASS-E3 (RCC FRAMED STRUCTURE)	18
XII	GODOWN	19
XIII	Building built with brick work in mud mortar and partly with RR masonry in mud mortar and brick jelly concrete in lime for foundation and ordinary flooring; roofing with RCC / Madras Terrace in which country wood has been used throughout	20
XIV	THATCHED / TILED ROOF	21
XV	GARAGE BUILDINGS	22
XVI	MISCELLANEOUS ITEMS	23 to 25
XVII	FOR EXTERNAL SERVICES AND FOR INTERNAL SERVICES	26
XVIII	ELECTRICAL ITEMS	27 & 28

Verified by RealEstate™

OFFICE OF THE ENGINEER-IN-CHIEF, CHIEF ENGINEER (GENERAL) & CHIEF ENGINEER, CHENNAI REGION, PWD, CHEPAUK, CHENNAI-5

ANNEXURE-I

COMMON SCHEDULE OF PLINTH AREA RATES FOR THE VALUATION OF BUILDINGS FOR RENTAL CALCULATION PURPOSE BY PWD AND FOR THE PURPOSE OF COLLECTION OF STAMP DUTY BY REGISTRATION DEPARTMENT DURING THE YEAR 2022-2023 [WITH EFFECT FROM 16.08.2022]

The Common Schedule of Plinth Area Rates for the Valuation of Buildings with reference to the plinth area for each type of construction (excluding cost of land) shall be arrived at as given below.	
General Note to be followed in arriving at the Rental Valuation of Buildings	
a	The rates approved and furnished below vide Sl. No. I to XVIII are applicable commonly to the entire State, subject to the following provisions:
i	An extra 20% shall be added to the rates approved vide Sl. No. I to XV below for valuation of Buildings within Chennai Corporation limits and its belt area of 32 km around Chennai Corporation limit.
ii	An extra 15% shall be added to the rates approved vide Sl. No. I to XV below for Valuation of Buildings within Coimbatore, Erode and Tiruppur Corporation limits.
iii	An extra 10% shall be added to the rates approved vide Sl. No. I to XV below for Valuation of Buildings within Corporation limits of Trichy, Madurai, Salem, Tirunelveli, Thoothukudi, Vellore, Thanjavur, Dindigul, Hosur, Nagercoil and Avadi.
iv	An extra 5% shall be added to the rates approved vide Sl. No. I to XV below for Valuation of Buildings within all Municipal limits.
v	An extra 10% shall be added to the rates approved vide Sl. No. I to XV below for Valuation of Buildings located in Nilgiris, Kodaikanal and Yercaud Hills, where tourist attractions are more.
b	The Field Officers are requested to follow the instructions contained in G.O.Ms.No.51, Finance (Salaries) Department, dated 01.03.2017 in fixation of either new rent or renewal of rent scrupulously, so that there shall not be any extra financial burden to the Government towards the payment of rent to the Private Buildings occupied by the Government Offices.
c	**Load Bearing Structure:** Building with masonry walls (stone or brick) to carry the loads from slabs without RCC (or) steel columns.
d	**Framed Structure:** Building with frames comprising of RCC (or) steel columns and beams to carry the loads from slabs.

Verified RealEstate ™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
I	**CLASS-A (LOAD BEARING STRUCTURE)**		
	Building built with **brick work in lime mortar (or) cement mortar** in which **teak wood** has been used throughout		
1	**Roof with RCC Slab**		
a	Ground Floor	Sq.m.	10465.00
b	First Floor	Sq.m.	9700.00
c	Second Floor	Sq.m.	9875.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
2	**Roof with Madras Terrace**		
a	Ground Floor	Sq.m.	9570.00
b	First Floor	Sq.m.	8970.00
c	Second Floor	Sq.m.	9125.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
3	**Roof with Mangalore Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	7610.00
b	First Floor	Sq.m.	7025.00
c	Second Floor	Sq.m.	7160.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
4	**Roof with Plain Mangalore Tiles**		
a	Ground Floor	Sq.m.	7160.00
b	First Floor	Sq.m.	6560.00
c	Second Floor	Sq.m.	6710.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
5	**Roof with Pan Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	7025.00
b	First Floor	Sq.m.	6425.00
c	Second Floor	Sq.m.	6560.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20

Verified RedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
6	**Roof with Pan Tiles without Flat Tiles**		
a	Ground Floor	Sq.m.	6275.00
b	First Floor	Sq.m.	5665.00
c	Second Floor	Sq.m.	5810.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
7	**Roof with AC Sheet**		
a	Ground Floor	Sq.m.	5910.00
b	First Floor	Sq.m.	5310.00
c	Second Floor	Sq.m.	5470.00
d	Other upper floors (add extra for each floors)	Sq.m.	117.00
8	**Roof with GI Sheet**		
a	Ground Floor	Sq.m.	6070.00
b	First Floor	Sq.m.	5470.00
c	Second Floor	Sq.m.	5610.00
d	Other upper floors (add extra for each floors)	Sq.m.	117.00
	RATE OF DEPRECIATION		**1%**

Verified RedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
II	**CLASS-A1 (LOAD BEARING STRUCTURE)**		
	Building built with **brick work in lime mortar (or) cement mortar** in which **country wood** has been used throughout		
1	**Roof with RCC Slab**		
a	Ground Floor	Sq.m.	9410.00
b	First Floor	Sq.m.	8510.00
c	Second Floor	Sq.m.	8685.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
2	**Roof with Madras Terrace**		
a	Ground Floor	Sq.m.	8510.00
b	First Floor	Sq.m.	7770.00
c	Second Floor	Sq.m.	7910.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
3	**Roof with Mangalore Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	6710.00
b	First Floor	Sq.m.	5810.00
c	Second Floor	Sq.m.	5960.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
4	**Roof with Plain Mangalore Tiles**		
a	Ground Floor	Sq.m.	6120.00
b	First Floor	Sq.m.	5360.00
c	Second Floor	Sq.m.	5520.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
5	**Roof with Pan Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	5960.00
b	First Floor	Sq.m.	5360.00
c	Second Floor	Sq.m.	5520.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20

Verified PedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
6	**Roof with Pan Tiles without Flat Tiles**		
a	Ground Floor	Sq.m.	5360.00
b	First Floor	Sq.m.	4755.00
c	Second Floor	Sq.m.	4905.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
7	**Roof with AC Sheet**		
a	Ground Floor	Sq.m.	5470.00
b	First Floor	Sq.m.	4865.00
c	Other upper floors (add extra for each floors)	Sq.m.	117.00
8	**Roof with GI Sheet**		
a	Ground Floor	Sq.m.	5705.00
b	First Floor	Sq.m.	5095.00
c	Other upper floors (add extra for each floors)	Sq.m.	117.00
	RATE OF DEPRECIATION		**1%**

Verified RedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
III	**CLASS-B (LOAD BEARING STRUCTURE)**		
	Building built with **brick work in lime mortar (or) cement mortar & partly mud mortar** in which **teak wood** has been used throughout		
1	**Roof with RCC Slab**		
a	Ground Floor	Sq.m.	8510.00
b	First Floor	Sq.m.	7770.00
c	Second Floor	Sq.m.	7925.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
2	**Roof with Madras Terrace**		
a	Ground Floor	Sq.m.	7610.00
b	First Floor	Sq.m.	7025.00
c	Second Floor	Sq.m.	7160.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
3	**Roof with Mangalore Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	5960.00
b	First Floor	Sq.m.	5205.00
c	Second Floor	Sq.m.	5360.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
4	**Roof with Plain Mangalore Tiles**		
a	Ground Floor	Sq.m.	5520.00
b	First Floor	Sq.m.	4755.00
c	Second Floor	Sq.m.	4905.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
5	**Roof with Pan Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	5225.00
b	First Floor	Sq.m.	4625.00
c	Second Floor	Sq.m.	4755.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20

Verified PedlEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
6	**Roof with Pan Tiles without Flat Tiles**		
a	Ground Floor	Sq.m.	4755.00
b	First Floor	Sq.m.	4155.00
c	Second Floor	Sq.m.	4305.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
7	**Roof with AC Sheet**		
a	Ground Floor	Sq.m.	4855.00
b	First Floor	Sq.m.	4270.00
c	Other upper floors (add extra for each floors)	Sq.m.	117.00
8	**Roof with GI Sheet**		
a	Ground Floor	Sq.m.	5020.00
b	First Floor	Sq.m.	4420.00
c	Other upper floors (add extra for each floors)	Sq.m.	117.00
	RATE OF DEPRECIATION		**1.50%**

Verified by RealEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
IV	**CLASS-B1 (LOAD BEARING STRUCTURE)**		
	Building built with **brick work in lime mortar (or) cement mortar and partly in mud mortar** in which **country wood** has been used throughout		
1	**Roof with RCC Slab**		
a	Ground Floor	Sq.m.	7770.00
b	First Floor	Sq.m.	7025.00
c	Second Floor	Sq.m.	7160.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
2	**Roof with Madras Terrace**		
a	Ground Floor	Sq.m.	6875.00
b	First Floor	Sq.m.	6270.00
c	Second Floor	Sq.m.	6425.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
3	**Roof with Mangalore Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	5360.00
b	First Floor	Sq.m.	4755.00
c	Second Floor	Sq.m.	4905.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
4	**Roof with Plain Mangalore Tiles**		
a	Ground Floor	Sq.m.	4905.00
b	First Floor	Sq.m.	4305.00
c	Second Floor	Sq.m.	4475.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
5	**Roof with Pan Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	4625.00
b	First Floor	Sq.m.	4005.00
c	Second Floor	Sq.m.	4155.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20

Verified PedlEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
6	**Roof with Pan Tiles without Flat Tiles**		
a	Ground Floor	Sq.m.	4475.00
b	First Floor	Sq.m.	3875.00
c	Second Floor	Sq.m.	4005.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
7	**Roof with AC Sheet**		
a	Ground Floor	Sq.m.	4570.00
b	First Floor	Sq.m.	3980.00
c	Other upper floors (add extra for each floors)	Sq.m.	117.00
8	**Roof with GI Sheet**		
a	Ground Floor	Sq.m.	4230.00
b	First Floor	Sq.m.	4120.00
c	Other upper floors (add extra for each floors)	Sq.m.	117.00
	RATE OF DEPRECIATION		**2%**

Verified PedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
V	**CLASS-C (LOAD BEARING STRUCTURE)**		
	Building built with **brick work in mud mortar** in which **country wood** has been used throughout		
1	**Roof with RCC Slab**		
a	Ground Floor	Sq.m.	6600.00
b	First Floor	Sq.m.	5810.00
2	**Roof with Madras Terrace**		
a	Ground Floor	Sq.m.	5960.00
b	First Floor	Sq.m.	5360.00
3	**Roof with Mangalore Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	4625.00
b	First Floor	Sq.m.	4155.00
4	**Roof with Plain Mangalore Tiles**		
a	Ground Floor	Sq.m.	4155.00
b	First Floor	Sq.m.	3715.00
5	**Roof with Pan Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	4005.00
b	First Floor	Sq.m.	3580.00
6	**Roof with Pan Tiles without Flat Tiles**		
a	Ground Floor	Sq.m.	3715.00
b	First Floor	Sq.m.	3405.00
7	**Roof with AC Sheet**		
a	Ground Floor	Sq.m.	4120.00
b	First Floor	Sq.m.	3670.00
8	**Roof with GI Sheet**		
a	Ground Floor	Sq.m.	4270.00
b	First Floor	Sq.m.	3820.00
	RATE OF DEPRECIATION		**2%**

Verified RediEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
VI	**CLASS-D (LOAD BEARING STRUCTURE)**		
	Building built with **brick work in lime or cement mortar** in which **partly wood and partly steel** has been used throughout		
1	**Roof with RCC Slab**		
a	Ground Floor	Sq.m.	6885.00
b	First Floor	Sq.m.	5960.00
c	Second Floor	Sq.m.	6120.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
2	**Roof with Madras Terrace**		
a	Ground Floor	Sq.m.	6120.00
b	First Floor	Sq.m.	5520.00
c	Second Floor	Sq.m.	5665.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.00
3	**Roof with Mangalore Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	4755.00
b	First Floor	Sq.m.	4305.00
c	Second Floor	Sq.m.	4475.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
4	**Roof with Plain Mangalore Tiles**		
a	Ground Floor	Sq.m.	4305.00
b	First Floor	Sq.m.	3875.00
c	Second Floor	Sq.m.	4005.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
5	**Roof with Pan Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	4155.00
b	First Floor	Sq.m.	3715.00
c	Second Floor	Sq.m.	3875.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20

Verified RegiEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
6	**Roof with Pan Tiles without Flat Tiles**		
a	Ground Floor	Sq.m.	3875.00
b	First Floor	Sq.m.	3580.00
c	Second Floor	Sq.m.	3685.00
d	Other upper floors (add extra for each floors)	Sq.m.	118.20
7	**Roof with AC Sheet**		
a	Ground Floor	Sq.m.	4270.00
b	First Floor	Sq.m.	3670.00
c	Other upper floors (add extra for each floors)	Sq.m.	117.00
8	**Roof with GI Sheet**		
a	Ground Floor	Sq.m.	4430.00
b	First Floor	Sq.m.	3980.00
c	Other upper floors (add extra for each floors)	Sq.m.	117.00
	RATE OF DEPRECIATION		**1.50%**

Verified PedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
VII	**CLASS-D1 (LOAD BEARING STRUCTURE)**		
	Building built with **brick in lime or cement mortar** in which **steel frame** is used throughout		
1	**Roof with RCC Slab**		
a	Ground Floor	Sq.m.	7035.00
b	First Floor	Sq.m.	6265.00
c	Second Floor	Sq.m.	6425.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.90
2	**Roof with Madras Terrace**		
a	Ground Floor	Sq.m.	6425.00
b	First Floor	Sq.m.	5795.00
c	Second Floor	Sq.m.	5945.00
d	Other upper floors (add extra for each floors)	Sq.m.	149.90
3	**Roof with Mangalore Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	5030.00
b	First Floor	Sq.m.	4570.00
c	Second Floor	Sq.m.	4720.00
d	Other upper floors (add extra for each floors)	Sq.m.	122.90
4	**Roof with Plain Mangalore Tiles**		
a	Ground Floor	Sq.m.	4570.00
b	First Floor	Sq.m.	4120.00
c	Second Floor	Sq.m.	4255.00
d	Other upper floors (add extra for each floors)	Sq.m.	122.90
5	**Roof with Pan Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	4420.00
b	First Floor	Sq.m.	3960.00
c	Second Floor	Sq.m.	4120.00
d	Other upper floors (add extra for each floors)	Sq.m.	122.90

Verified RedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
6	**Roof with Pan Tiles without Flat Tiles**		
a	Ground Floor	Sq.m.	4120.00
b	First Floor	Sq.m.	3780.00
c	Second Floor	Sq.m.	3930.00
d	Other upper floors (add extra for each floors)	Sq.m.	122.90
7	**Roof with AC Sheet**		
a	Ground Floor	Sq.m.	4515.00
b	First Floor	Sq.m.	3915.00
c	Other upper floors (add extra for each floors)	Sq.m.	121.70
8	**Roof with GI Sheet**		
a	Ground Floor	Sq.m.	4680.00
b	First Floor	Sq.m.	4210.00
c	Other upper floors (add extra for each floors)	Sq.m.	121.70
	RATE OF DEPRECIATION		**1%**

Verified PedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
VIII	**CLASS-E (RCC FRAMED STRUCTURE)**		
1	Framed structure building **built in cement mortar** in which **teak wood joineries** is used for construction (excluding water supply, sanitary and electrical installations)		
a	Ground Floor	Sq.m.	11800.00
b	First Floor	Sq.m.	11025.00
c	Second Floor	Sq.m.	11175.00
d	Third Floor	Sq.m.	11340.00
e	Other upper floors (add extra for each floors)	Sq.m.	152.50
2	Balcony / Portico projecting outside the face of the building with hand rail with brick work/wood/grill	Sq.m.	4025.00
	RATE OF DEPRECIATION		**1%**

Verified RealEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
IX	**CLASS-E1 (RCC FRAMED STRUCTURE)**		
1	Framed structure building **built in cement mortar** in which **country wood joineries** is used for construction (excluding water supply, sanitary and electrical installations)		
a	Ground Floor	Sq.m.	10750.00
b	First Floor	Sq.m.	9835.00
c	Second Floor	Sq.m.	9985.00
d	Third Floor	Sq.m.	10150.00
e	Other upper floors (add extra for each floors)	Sq.m.	152.50
2	Balcony / Portico projecting outside the face of the building with hand rail with brick work/wood/grill	Sq.m.	4025.00
	RATE OF DEPRECIATION		**1%**

Verified RealEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
X	**CLASS-E2 (RCC FRAMED STRUCTURE)**		
1	Framed structure building **built in cement mortar** in which **steel frame joineries** is used for construction (excluding water supply, sanitary and electrical installations)		
a	Ground Floor	Sq.m.	8360.00
b	First Floor	Sq.m.	7570.00
c	Second Floor	Sq.m.	7725.00
d	Third Floor	Sq.m.	7885.00
e	Other upper floors (add extra for each floors)	Sq.m.	152.50
2	Balcony / Portico projecting outside the face of the building with hand rail with brick work/wood/grill	Sq.m.	4025.00
	RATE OF DEPRECIATION		**1%**

Verified RealEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
XI	**CLASS-E3 (RCC FRAMED STRUCTURE)**		
1	Framed structure building **built in cement mortar** in which **partly wood joineries and partly steel joineries** is used for construction (excluding water supply, sanitary & electrical installations)		
a	Ground Floor	Sq.m.	8210.00
b	First Floor	Sq.m.	7285.00
c	Second Floor	Sq.m.	7430.00
d	Third Floor	Sq.m.	7580.00
e	Other upper floors (add extra for each floors)	Sq.m.	152.50
2	Balcony / Portico projecting outside the face of the building with hand rail with brick work/wood/grill	Sq.m.	4025.00
	RATE OF DEPRECIATION		**1%**

Verified RegiEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
XII	**GODOWN**		
2 a	For godowns / Hall type construction with RCC columns and connecting beams etc. with steel trusses and purlins		
	Roofing with AC Sheet	Sq.m.	8620.00
	Roofing with GI Sheet	Sq.m.	8940.00
b	For godowns / Hall type construction with load bearing type construction with steel trusses and purlins		
	Roofing with AC Sheet	Sq.m.	8000.00
	Roofing with GI Sheet	Sq.m.	8140.00
	RATE OF DEPRECIATION		**1%**

Verified RealEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
XIII	Building built with brick work in mud mortar and partly with RR masonry in mud mortar and brick jelly concrete in lime for foundation and ordinary flooring; roofing with RCC/Madras Terrace in which country wood has been used thoroughout		
1	**Roof with RCC slab**		
	Ground Floor	Sq.m.	7310.00
	First Floor	Sq.m.	6275.00
2	**Roof with Madras Terrace**		
a	Ground Floor	Sq.m.	6425.00
b	First Floor	Sq.m.	5520.00
3	**Roof with Mangalore Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	4905.00
b	First Floor	Sq.m.	4155.00
4	**Roof with Plain Mangalore Tiles**		
a	Ground Floor	Sq.m.	4475.00
b	First Floor	Sq.m.	3875.00
5	**Roof with Pan Tiles over Flat Tiles**		
a	Ground Floor	Sq.m.	4155.00
b	First Floor	Sq.m.	3580.00
6	**Roof with Pan Tiles without Flat Tiles**		
a	Ground Floor	Sq.m.	4005.00
b	First Floor	Sq.m.	3405.00
7	**Roof with AC Sheet**		
a	Ground Floor	Sq.m.	4270.00
b	First Floor	Sq.m.	3545.00
8	**Roof with GI Sheet**		
a	Ground Floor	Sq.m.	4430.00
b	First Floor	Sq.m.	3670.00
	RATE OF DEPRECIATION		**2.50%**

Verified RealEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
XIV	**THATCHED / TILED ROOF**		
1	Bulding built with brick work in clay and plastered with lime mortar or cement mortar, ordinary grano flooring, white or colour washed, thatched roof either with coconut leaves or palmyrah leaves over CW or bamboo rafters, etc.		
a	Ground Floor	Sq.m.	3380.00
2	Building built with plain mud walls plastered with mud mortar and thatched roof either with coconut leaves of palmyrah leaves over bamboo or country wood rafters etc.		
a	Ground Floor	Sq.m.	1680.00
3	Building built with plain mud walls and plastered with mud mortar & roof with mangalore tiles using bamboo or country wood rafters etc.	Sq.m.	2235.00
4	Building built with plain mud walls and plastered with mud mortar and roof with pan tiles using bamboo or country wood rafters	Sq.m.	1955.00
5	Building built with plain mud walls and plastered with mud mortar and roof with AC sheet	Sq.m.	2375.00
6	Building built with plain mud walls and plastered with mud mortar and roof with GI sheet	Sq.m.	2440.00
	RATE OF DEPRECIATION		**4%**

Verified by PeriEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
XV	**GARAGE BUILDINGS**		
a	Garage buildings built with brick work in lime or cement mortar and roof with RCC slab in which teak wood or rolling shutters used.	Sq.m.	4320.00
b	Garage building built with brick work in lime or cement mortar with mangalore tile or pan tile roof over flat tiles in which teak wood or rolling shutters used.	Sq.m.	4025.00
	RATE OF DEPRECIATION		**1%**
c	Garage buildings built with brick work in partly clay and partly lime or cement mortar and roof with RCC slab in which country wood used throughout.	Sq.m.	4305.00
d	Garage building built with brick work in partly clay and partly lime or cement mortar with mangalore tiles or pan tiles roof over flat tiles in which country wood used throughout.	Sq.m.	3715.00
	RATE OF DEPRECIATION		**2%**

Verified RealEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
XVI	**MISCELLANEOUS ITEMS**		
1	Open area paved either with cement concrete (or) brick (or) stone slabs with retaining walls	Sq.m.	843.00
2	Fencing the area with RCC post and covered either with barbed wire or chain link 1.65m height from Ground level.	RM	623.00
	RATE OF DEPRECIATION		**4%**
3	Construction of compound wall to a normal height of 1.50m from ground level with required number of gates, grills, etc.		
	i. With load bearing foundation with brick work in cement mortar 1:5	RM	4210.00
4	i. Mosaic Flooring Grey Colour Tiles	Sq.m.	827.00
	ii. Mosaic Flooring with Colour Tiles (other than Grey)	Sq.m.	932.00
	iii. Dadooing with Mosaic in Situ	Sq.m.	808.00
5	Cuddapah Slab / Shahabad Slab Flooring	Sq.m.	564.00
6	Flooring with Granite Slabs 18 to 20mm thick	Sq.m.	3085.00
7	i. Flooring with Vitrified Tiles	Sq.m.	1337.00
	ii. Dadooing with Vitrified Tiles	Sq.m.	1155.00
8	i. Flooring with Ceramic Tiles	Sq.m.	897.00
	ii. Dadooing with Ceramic / Glazed Tiles	Sq.m.	778.00
9	i. Flooring with Marble Tiles	Sq.m.	1535.00
	ii. Flooring with Marble Slabs		
	a. for Slab of size 1.20 metre and above	Sq.m.	2215.00
	b. for Slab of size below 1.20 metre	Sq.m.	1810.00
	RATE OF DEPRECIATION		
10	Iron gates (1.2m height & 3m width)		
	i. Iron gates with ornamental grill	Sq.m.	1970.00
	ii. Iron gates with GI pipe alround & weld mesh inbetween	Sq.m.	1240.00

Verified RegiEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
11	Rolling shutters	Sq.m.	2730.00
12	Over head tanks		
	i. In brick work / litre	Litre	17.70
	ii. PVC tanks / litre	Litre	5.55
	iii. In RCC / litre	Litre	19.95
13	Municipal Water Tap Service connection	Each	3510.00
14	Hand pump	Each	3510.00
15	Bore well		
	i. Upto 50 metre depth / m	RM	211.00
	ii. 50 to 100 metre depth	RM	224.00
	iii. 100 to 200 metre depth	RM	230.00
16	i. Open Well 1.20 metre dia with brick steining 7.50 metre deep	Each	21000.00
	ii. Open well 1.50 metre dia with brick steining 7.50 metre deep	Each	26260.00
	iii. Open well 1.80 metre dia with brick steining 7.50 metre deep	Each	31380.00
	iv. Open well 2.00 metre dia with brick steining 7.50 metre deep	Each	38140.00
17	i. False ceiling using aluminium tees, angles with particle board 60 x 60cm size	Sq.m.	1040.00
	ii. Using plywood 5mm thick	Sq.m.	731.00
18	Septic tank built in brick work in cement mortar precast cover slab with inlet and outlet (On volume basis)		
	for 1 Cu.m. capacity	Cu.m.	12195.00
19	Inspection chambers with RCC cover slab built in brick work in cement mortar, 23cm thick, plastered and finished		
	i. 60 x 60 x 60cm size	Each	2430.00
	ii. 60 x 60 x 75cm size	Each	2955.00
	iii. 60 x 60 x 90cm size	Each	3640.00

Verified RealEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
20	i. Providing IWC with water line, tap, flush out system etc.	Each	6000.00
	ii. Providing EWC 580mm with water line, tap, flush out system etc.	Each	7625.00
21	Wash basin including water line, tap, etc.	Each	2705.00
22	Provision of towel rod and mirror of size 550 x 440mm	Each	1227.00
23	Flat back urinal with water line, valves, etc	Each	1623.00
24	Sink with water line, tap, etc	Each	2705.00
25	Open latrine with 1.80 metre height wall built in brick work in cement mortar.	Sq.m.	3735.00
26	i. Bathroom with GI water line, taps, shower line etc. (minimum room size 1.50m x 1.35m)	Each	5360.00
	ii. Bathroom with PVC water line, tap, shower line, etc. (minimum room size 1.50m x 1.35m)	Each	4680.00
	iii. Bath Tub with all accessories (Porcelain)	Each	20000.00
	iv. Bath Tub with all accessories (built with mosaic finish)	Each	5360.00

Verified RealEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
XVII	**I. FOR EXTERNAL SERVICES**		
1	50mm dia CI pipe line and specials	RM	645.00
2	75mm dia CI pipe line and specials	RM	910.00
3	100mm dia SW pipe line and specials	RM	200.00
4	150mm dia SW pipe line and specials	RM	335.00
5	100mm dia PVC pipe line and specials	RM	380.00
6	75mm dia PVC pipe line and specials	RM	229.00
	II. FOR INTERNAL SERVICES		
1	Water supply arrangements (maximum)	on value of building	7.50%
2	Internal sanitary arrangements (maximum)	on value of building	7.50%
3	Interal electrical arrangements (maximum)	on value of building	7.50%

Verified RedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
XVIII	**ELECTRICAL ITEMS**		
1	Plug point	Each	322.00
2	Fan point	Each	385.00
3	Light point	Each	366.00
4	1.20m flourescent fitting patty type with tube		
	i. Single	Each	517.00
	ii. Double	Each	942.00
5	40 W flourescent tube (single)	Each	103.80
6	1.20m flourescent fitting box type with tube		
	i. Single	Each	738.00
	ii. Double	Each	1157.00
7	i. 1.20m sweep AC ceiling fan with regulator	Each	2525.00
	ii. 1.40m sweep AC ceiling fan with regulator	Each	2720.00
8	EXHAUST FAN	Each	2215.00
9	0.50 HP electric motor pump set		
	i. centrifugal	Each set	10570.00
	ii. Jet type	Each set	13510.00
10	1.00 HP electric motor pump set		
	i. Centrifugal	Each set	12870.00
	ii. Jet	Each set	15765.00
11	1.50 HP electric motor pump set		
	i. Centrifugal	Each set	15185.00
	ii. Jet	Each set	19950.00
12	2.00 HP electric motor pump set		
	i. Centrifugal	Each set	18790.00
	ii. Jet	Each set	24060.00
13	3.00 HP electric motor pump set		
	i. Centrifugal	Each set	23420.00
	ii. Jet	Each set	31540.00

Verified RedEstate™

Sl. No.	Type of construction	Unit	Rates approved for the year 2022-2023 (In Rupees)
14	5.00 H.P. electric motor pump set (JET)	Each set	38620.00
15	Air-conditioning (on floor area basis)		
	a. Non-Ductable	Sq.m.	5025.00
	b. Ductable	Sq.m.	6720.00
16	**i. 8 Persons Capacity Passenger Lift (GF + 3 Floors)**		
	a. Gearless Lift with Machine Room	Each	2008000.00
	b. Gearless Lift without Machine Room	Each	2098000.00
	ii. 10 Persons Capacity Passenger Lift (GF + 3 Floors)		
	a. Gearless Lift with Machine Room	Each	2098000.00
	b. Gearless Lift without Machine Room	Each	2201000.00
	iii. 13 Persons Capacity Passenger Lift (GF + 3 Floors)		
	a. Gearless Lift with Machine Room	Each	2330000.00
	b. Gearless Lift without Machine Room	Each	2446000.00
	iv. 20 Persons Capacity Passenger Lift (GF + 3 Floors)		
	a. Gearless Lift with Machine Room	Each	2895000.00
	b. Gearless Lift without Machine Room	Each	3090000.00

for Engineer-in-Chief,
Chief Engineer (General) &
Chief Engineer, Chennai Region,
PWD, Chennai-5.

12/8/2022

Verified © RealEstate™