







Plan showing the Proposed Construction of a Ground Floor and First Floor Residential Building in
S.F No: 4/1A1A1A1A, New Subdivision S.F No: 4/5, Patta No: 3001, Plot No : 14 West Part, at Piragathi Nagar,
S.Kannanur West Village, S.Kannanur Town Panchayat, Mannachanallur Taluk and Trichy District.



ENDT. B.A. NO. 15/24-25 DT. 16.08.2024
PLAN APPROVED

Subject to the Conditions as mentioned
in this Office B.A. No. 15/2024-2025
Dated 16.08.2024 for the Period
from 16.08.2024 To 16.08.2029

Approval seal

Schedule of Joinery

MD	: Main Door	: 1000 x 2135
D	: Door	: 900 x 2135
D1	: Door	: 800 x 2135
O	: Open	: 900 x 2135
W	: Window	: 1800 x 1800
W1	: Window	: 1200 x 1400
W2	: Window	: 1200 x 900
V	: Ventilator	: 900 x 600

Area statement :

AREA DETAILS	PL AREA SQ. M	NON PL AREA SQ. M	TOTAL AREA SQ. M	TOTAL PER AREA SQ. M
AREA OF THE SITE	-	-	188.60	2030.00
GROUND FLOOR AREA	71.41	-	71.41	768.67
FIRST FLOOR AREA	15.62	-	15.62	168.13
TOTAL AREA	87.03	-	87.03	936.80
OPEN LEFT	-	-	117.19	1261.33

PLOT COVERAGE = $71.41 / 188.60 \times 100 = 37.86\%$

FLOOR SPACE INDEX (F.S.I) ($87.03 / 188.60$) = 0.461

Notes :

- All dimensions are in meter.
- Scale : 1" = 8' 0" (1:100)
- Waste water will be utilized for garden purpose.
- Boundary shown in Green. — ○
- Proposal shown in Red — ○

Owner : T.BASKARAN.

Applicant

Registered Engineer / Licensed Surveyor

Reg. No. 101/2018