







Plan showing the Proposed Construction of a Ground Floor and First Floor Residential Building in
S.F No: 115/B & 118/1A, UDR S.F No: 227/9, Patta No: A3, at Anna Nagar,
S.Kannanur West Village, S.Kannanur Town Panchayat, Mannachanallur Taluk and Trichy District.



RCC Roof slab
in 1:2:4 mix
R.C.C.Lintel cum
sunshade in 1:2:4 mix
Brickwork in CM 1:5 &
plastering with CM 1:5
RCC Roof slab
in 1:2:4 mix
R.C.C.Lintel cum
sunshade in 1:2:4 mix
Brickwork in CM 1:5 &
plastering with CM 1:5
Floor finishing
using Vitrified tiles
PCC 1:5:10
sand
filling



Approval seal

Schedule of Joinery

MD	: Main Door	: 1000 x 2135
D	: Door	: 900 x 2135
D1	: Door	: 800 x 2135
O	: Open	: 900 x 2135
W	: Window	: 1800 x 1800
W1	: Window	: 1200 x 1400
W2	: Window	: 1200 x 900
V	: Ventilator	: 900 x 600

Area statement :

AREA DETAILS	F.S. AREA SQ.M	NOT F.S. AREA SQ.M	TOTAL AREA SQ.M	TOTAL FLOOR AREA SQ.FT
AREA OF THE SITE	-	-	105.00	1130.00
GROUND FLOOR AREA	64.12	-	64.12	690.20
FIRST FLOOR AREA	64.12	-	64.12	690.20
TOTAL AREA	128.24	-	128.24	1380.40
OPEN LEFT	-	-	40.88	439.80

PLOT COVERAGE = 64.12 / 105.00 X 100 = 61.06 %

FLOOR SPACE INDEX (F.S.I) (128.24 / 105.00) = 1.221

Notes :

All dimensions are in meter.
Scale : 1"= 8' 0" (1:100)
Waste water will be utilized for garden purpose.
Boundary shown in Green.
Proposal shown in Red

Applicant

Er. S. HARIHARAN, DCE.,
Consulting Civil Engineer,
Licensed Surveyor
HD CONTRACTORS
Samayapuram, Cell: 9095953727
Registered Engineer / Licensed Surveyor