







PLAN SHOWING THE PROPOSED CONSTRUCTION OF GROUND AND FIRST FLOOR RCC ROOF

COMMERCIAL SHOP BUILDING IN S.F.NO.249/16, PLOT NO.34, PATTAN NO.4161 AT

VENGADAKRISHNAPURAM VILLAGE AND PANCHAYAT OF ARIYALUR TALUK AND DISTRICT.

(SCALE 1:100)



SCHEDULE OF JOINERIES:		
TYPE	REFERENCE	SIZE IN METER
RS	ROLLING SHUTTER	4.70 x 2.13
D	FLUSH DOOR	1.00 x 2.13
D1	FLUSH DOOR	0.76 x 2.13
D2	FLUSH DOOR	1.00 x 1.98
O	OPEN	1.00 x 2.13
W1	WINDOW	1.53 x 1.52
W2	WINDOW	1.22 x 1.52
W3	WINDOW	0.91 x 1.52
V	VENTILATOR	1.20 x 0.60
J	JALY	0.91 x 1.83

AREA DETAILS		
DESCRIPTION		SQ.M
PLOT AREA (as per Document)		167.22
PLOT AREA (as per FMB)		167.22
SUPER IMPOSED PLOT AREA		167.22
DESCRIPTION	F.S.I AREA (in SQ.M)	NON F.S.I AREA (in SQ.M)
PROPOSED BUILDING PLINTH AREA		
GROUND FLOOR AREA	91.34	-
FIRST FLOOR AREA	91.34	-
HEAD ROOM AREA	-	-
TOTAL AREA	182.68	-
OPEN SPACE AREA		75.88

PLOT COVERAGE	=	$\frac{91.34}{167.22} \times 100 = 54.62\%$
F.S.I	=	$\frac{182.68}{167.22} = 1.09$

- PARKING**
- TWO WHEELER PARKING SPACE 2 NOS PROVIDED.
 - CAR PARKING SPACE 1 NOS PROVIDED.
- NOTES:**
- FIRE EXTINGUISHER
 - ALL DIMENSION ARE IN METER
 - SCALE - 1:100
 - WASTE WATER UTILISED FOR GARDEN PURPOSE.
 - SOLAR WATER HEATER PROVIDED IN TERRACE FLOOR.

COLOUR INDEX:	
BOUNDARY SHOWN IN GREEN	
PROPOSED BUILDING IN RED	

A.S.A Constructions
Chinna Aranmanal Street, Ariyalur.
Mobile : 9443303157, 9943425641

APPLICANT

[Signature]
Mrs. ANITHA
W/O. Mr. PARAMASIVAM.

ENGINEER

[Signature]
Er.D.SEETHA, M.E(Struct),MBA.,
LICENSED SURVEYOR NO:329
REGISTERED ENGINEER GRADE -1
RE/PLBR/APR 2019/014