



तमिलनाडु TAMILNADU
22 JUN 2026

ES 670778

D. MURALI
STAMP VENDOR

No. : 15915/B5/B3/08
HIGH COURT CAMPUS

CHENNAI - 600 104. PH : 044-2644 1710

Krishnamoorthy and Others
Chennai - 600069.

Indemnity Affidavit

I, **Krishnamoorthy and Others**, Owner and Proprietor of the project named as "**SRI BALAJI NAGAR PHASE-I**" residing at No.2/193, School Street, Sikkarayapuram, Kundrathur, Kancheepuram District, Chennai-600069, do hereby solemnly affirm and sincerely state as follows:


1. I state that I have applied RERA approval for layout of "**SRI BALAJI NAGAR PHASE-I**" comprised in Survey No: 159 measuring an extent of 4550 Sq.mts (48976.2 Sq.feet) situated in Sikkarayapuram Village, Kundrathur Panchayat, Kundrathur Panchayat Union, Kundrathur Taluk, Kanchipuram District, Tamil Nadu., within the limit of Greater Chennai Corporation before the Tamil Nadu Real Estate Regulatory Authority.



[Signature]
M. Ashu.
M.A.

1. As per The Chief Engineer (WRD) conditions, I have completed all the conditions properly laid by WRD as mentioned in WRD letter No.DB/T5(3)/F-NOC/9410 (Chikkarayapuram Village) /10762 /2025 / dated 16.12.2025.
2. We hereby taking responsibilities and agrees to indemnify future potential allottees in this project if any losses. Hence, Kindly issue the approval Certificate (Form-C).

Solemnly affirmed at Chennai
On this the 30th day of June 2026
and signed his name in my presence.




M. Ashu.

Deponent



Before Me



R. KRISHNAMOORTHY, M.A., M.L.,
Advocate & Notary Public
ADVOCATE & ASSOCIATION
HIGH COURT. MADRAS - 600 104.



Water Resources Department

From
Er.C.Podupani Thilagam, M.E.,
 Chief Engineer, WRD,
 Chennai Region,
 Chepauk, Chennai-5.

Mail Id: cecrwrhdho@gmail.com

To
The Member Secretary,
 Chennai Metropolitan Development Authority,
 No.1, Gandhi Irwin Road,
 Egmore, Chennai-8.

Lr.No.DB /T5(3)/ F NOC 9410Chikkarayapuram Village10762 /2025/ Dated.16.12.2025.
Sir,

Sub: CMDA – APU – Layout Division – Laying out of house sites in the property comprised in S.F.No.159 of Chikkarayapuram Village, Kundrathur Taluk, Kancheepuram District, Kundrathur Panchayat Union Limit - Specific Remarks along with NOC on inundation point of view along with Permissibility for Temporary Permission for Construction of a RCC Culvert across the Channel in S.F.No.158 so as to access from his land S.No.159 to Existing Layout Road S.No.156 of Chikkarayapuram Village – issued – regarding.

Ref: 1. The Member Secretary, Chennai Metropolitan Development Authority, Gandhi Irwin Road, Egmore, Chennai – 600 008 Letter No. Layout – 1 / 0277 / 2025 / Dated: 24.09.2025.

With reference to the 1st letter cited above and after careful consideration the technical opinion and NOC on inundation point of view of this department is hereby accorded for Temporary Permission for Construction of a RCC Culvert across the Channel in S.F.No.158 so as to access from his land S.No.159 to Existing Layout Road S.No.156 of Chikkarayapuram Village and technical opinion along with NOC on inundation point of view for Laying out of house sites in the property comprised in S.F.No.159 of Chikkarayapuram Village, Kundrathur Taluk, Kancheepuram District, Kundrathur Panchayat Union Limit in favour of Thiruvallargal.S.M.Krishnamoorthy & 2 others, Sons of S.K.Mahalingam, No.2/193, School Street, Chikkarayapuram, Kundrathur, Kancheepuram District, Pincode – 600 069.

The proposed site in S.F.No.159 was inspected and ascertained such that, applicant's land is surrounded by Government Channels (ie., Chikkarayapuram branch channel) in S.F.No.157 & 160, S.F.No.158 and S.F.No.161 abutting the site on Western side, Southern side and Northern side respectively. These Government channels originate from Chembrambakkam Lake Sluice No.5 traversing from West to East direction, wherein the main channel bifurcates into the Chikkarayapuram branch channel. Further, the Kundrathur – Poonamallee Main Road and Outer Ring Road traverses on Eastern side and Western side of the site respectively, both not abutting the site.


 16/12/25

In connection to this, the Government land classified as "Tharisu" in S.F.No.199/1 lies close proximity to the applicant's land in Southern side. Consequently, any encroachment upon these government lands would be the responsibility of the applicant, and it is imperative that the concerned Revenue authorities / CMDA should verify and ensure compliance with the above mentioned Revenue records. It is crucial to emphasize that any encroachment upon Government land or Water bodies should be avoided.

Furthermore, according to the CMDA's Second Master Plan, the applicant's land falls under the "Mixed Residential Zone" classification. Also, the applicant's site is surrounded with Vacant lands on all directions, wherein at present, there are no irrigation activities and these channels act as Flood water drain channels due to vast urbanization and are classified as "Dry" lands as per Revenue records.

In order to ascertain the gravity of inundation of the said lands, the field levels were taken with reference to the Bench Mark from Known Datum of Sill Level of Sluice No.5 of Chembarambakkam Tank which is (+)18.560 m.

As a safety measure, the proposed site must be analyzed with respect to the flood levels experienced during previous past floods. The Observed Maximum Flood Level near the applicant's site was (+) 19.900 m, wherein there was water logging in the site and the flood water drained within a few days. The Top level of the Existing Layout Road is (+) 19.700 m, which is on Southern side of the Applicant's land. The FSL of the adjacent Government Channel in S.F.No.158 and S.F.No.160 is (+) 19.600 m & (+) 19.450 m respectively.

To protect the site safe against any inundation in the near future, the site must be raised to a level of 0.75m above the maximum flood level with respect to the past flood. Hence, it is recommended to raise the field level to (+) $19.900 + 0.75 = (+) 20.650$ m (ie., (+) 2.090 above the Sill Level of Sluice No.5 of Chembarambakkam Tank which is (+)18.560 m.) The field levels were taken at the proposed site and furnished for reference as below:

Sl. No.	Field Survey Number	Existing Field Level in m	Required height of filling with respect to the past flood level (+) $19.900 + 0.75 = (+) 20.650$ m	
			Required Level in m	Height Filling in m
1.	159 (North side)	18.510	(+) 20.650	2.140
2.	159 (South side)	18.340		2.310
3.	159 (East side)	18.380		2.270
4.	159 (West side)	18.150		2.500

Handwritten signature and date: 16/12/25

Also the proposed land is to be raised from 2.140 m to 2.500 m with hard earth with proper consolidation to avoid inundation problem during rainy season from the above existing field levels, the required filling varies from 2.140 m to 2.500 m to avoid inundation. Since, the existing field level is below MFL and the applicant is suggested not to have regular habitation below MFL.

As per the village plan, it has been observed that the Government Channel running through S.F.No.158 of Chikkarayapuram Village abuts the applicant's land on the Southern side, wherein there are no access roads in the surrounding areas to facilitate movement.

Henceforth, a RCC Culvert have been proposed at essential location in channel S.F.No.158 of Chikkarayapuram Village, so as to access from the applicant's site in S.F.No.159 to the Existing 7.2m wide Layout Road of Chikkarayapuram Village.

Hydraulic Particulars of the proposed RCC Culvert :

Full Supply Level of Channel (FSL)	: (+) 19.600 m
MFL near applicant's site	: (+) 19.900 m
Existing Bed Level	: (+) 18.200 m
Proposed Bed Level	: (+) 17.600 m
Top Level of the Existing Layout Road	: (+) 19.700 m
Bottom of Deck slab of proposed Culvert	: (+) 20.650 m

The bed level of the Culvert should be fixed in presence of the Executive Engineer concerned and only after the existing channel original bed level is ascertained and restored for flow from its respective directions.

S. No	Channel S.F.No.	Access to S.F.No.		Proposed Bed level in 'm' (+)	FSL in 'm' (+)	Minimum Inner Width of channel in 'm' as per FMB Average	Minimum Inner Vent height in 'm' or bottom level of Deck slab	Width of Culvert in 'm'	Area of Culvert in Sq.m	No. of vents allowed
		From	To							
1.	158	159	Existing Layout Road in S.F.No. 156/1	17.600	19.600	5.00	3.050 / 20.650	7.200	36.00	1 No.
Total									36.00 sq.m	

The applicant should adhere the above levels without causing any hindrance to free flow of water in the Government Channel.

Handwritten signature 16/12/25

Based on the request of the applicant and in view of the present site condition with respect to the available Revenue records for the Temporary Permission for Construction of a RCC Culvert across the Channel in S.F.No.158 so as to access from his land S.No.159 North to Existing Layout Road S.No.156/1 on South of Chikkarayapuram Village and technical opinion along with NOC on inundation point of view for Laying out of house sites in the property comprised in S.F.No.159 of Chikkarayapuram Village, Kundrathur Taluk, Kancheepuram District, Kundrathur Panchayat Union Limit may be issued in favour of Thiruvallargal.S.M.Krishnamoorthy & 2 others, Sons of S.K.Mahalingam, No.2/193, School Street, Chikkarayapuram, Kundrathur, Kancheepuram District, Pincode – 600 069 is hereby issued subject to the following conditions and technical suggestions, besides any other mandatory clearance of statutory permission from any other organization or department if necessary, for the consideration of Planning permission by Chennai Metropolitan Development Authority.

CONDITIONS:

1. The Proposed Culvert should be made of RCC of size and in S.F.No.158 of Chikkarayapuram Village earmarked in the sketch for temporary occupation for three years from the date of agreement. Only if the applicant's land on North and road on South available on both sides of the Government Channel / Odai, this permission is eligible for construction of Culvert.
2. The Proposed Culvert shall be made up of RCC Type with a minimum vent inner size, width and height of Bridge are specified below should be well within the boundary. The size & sill level of the proposed RCC Culvert Should be maintained as mentioned below in the specified S.F.No. and should be got executed only in the presence of WRD officials. The bed level of the Culverts should be fixed in presence of the Executive Engineer concerned only after the existing Government Channel original bed level ascertained and restored for the free flow direction from its origin.

Hydraulic Particulars of the proposed RCC Culvert :

Full Supply Level of Channel (FSL)	: (+) 19.600 m
MFL near applicant's site	: (+) 19.900 m
Existing Bed Level	: (+) 18.200 m
Proposed Bed Level	: (+) 17.600 m
Top Level of the Existing Layout Road	: (+) 19.700 m
Bottom of Deck slab of proposed Culvert	: (+) 20.650 m

Handwritten signature and date: 16/12/25

S. No	Channel S.F.No.	Access to S.F.No.		Proposed Bed level in 'm' (+)	FSL in 'm' (+)	Minimum Inner Width of channel in 'm' as per FMB Average	Minimum Inner Vent height in 'm' or bottom level of Deck slab	Width of Culvert in 'm'	Area of Culvert in Sq.m	No. of vents allowed
		From	To							
1.	158	159	Existing Layout Road in S.F.No. 156/1	17.600	19.600	5.00	3.050 / 20.650	7.200	36.00	1 No.
								Total	36.00 sq.m	

3. Based on the hydraulic particulars mentioned above, the design and drawings of the proposed RCC Culvert should be obtained from the Qualified Structural Engineer and the same should be submitted to the Executive Engineer, WRD., Kosasthalaiyar Basin Division, Thiruvallur, for getting approval before the commencement of work regarding hydraulic particulars. The work schedule for the above proposal should be informed to the Executive Engineer, WRD., Kosasthalaiyar Basin Division, Thiruvallur for monitoring and also completion of RCC Culvert should be reported to the Executive Engineer.

4. The Government Channel in S.F.No.158 running abutting the applicant's land on Southern, Western and Northern side should be completely desilted and resectioned by constructing retaining wall on both side of the Government Channel along entire boundary as per the FMB at the applicant's own cost.

5. The applicant should clearly demarcate their boundary especially Southern, Western and Northern side of Channel in S.F.No.158 before the commencement of any developmental activities in presence of Revenue authorities and WRD authorities concerned without fail and should not encroach the Channel abutting the land. Moreover, the width of entire Government Channel as per Revenue records (FMB) along & within the stretch of applicant's land should be maintained properly without any change and no encroachments at any cost.

6. The Government Channel abutting the applicant's boundary on Southern, Western and Northern side should be marked as per FMB and monitored and maintained by the applicants at their own cost. The width of the Government Channel should be maintained without encroachments as per Revenue records and the hydraulic parameters of the Government Channel should be maintained. The applicants should make necessary periodical arrangements for free flow of water through the existing Government Channel to the downside area within the proposed site. Also, the

Handwritten signature and date: 16/12/25

applicants should de-silt the Government Channel periodically and remove the obstruction then and there without any hindrance for free flow of water at their own cost within the proposed land, after the completion of project.

7. The applicant should pay an annual lease rent of Rs.80,000/- (Rupees Eighty thousand only) for utilising Government land of 36.00 sq.m., in the shape of Demand Draft drawn in favour of the Executive Engineer, WRD., Kosasthalaiyar Basin Division, Thiruvallur and it should be paid at one lumpsum for three years of Rs.2,40,000/- (Rupees Two Lakh and Forty Thousand only) in advance before the commencement of work. During execution / after construction of above Culvert, if any deviations are noted in above measurements, accordingly the lease rent also are to be revised respectively.
8. The applicant has to pay Service tax, GST etc., separately as per norms in existence and as amended from time to time without fail.
9. The applicant should execute the lease agreement with Executive Engineer, WRD., Kosasthalaiyar Basin Division, Thiruvallur before commencing the work and it should be renewed once in three years for which the applicant voluntarily has to apply within 2 months, before the expiry of the lease period. The lease rent is subjected to revision from time to time as per guideline value / Government orders.
10. The applicant is also to pay the caution deposit of sum of Rs.2,00,000/- (Rupees Two lakh only) in favour of the Executive Engineer, WRD., Kosasthalaiyar Basin Division, Thiruvallur, which will be refunded only after completion of six months on the certificate from concerned Assistant Executive Engineer of this department that the construction work (Culvert, Government Channel & retaining wall) was completed without any damage to the Government property or the damage caused during execution if any, will be rectified fully by the applicant. If failed, the cost of restoration work will be borne from the caution deposit.
11. The applicant should not claim any privilege on the above leased portion of the land (Culvert land, Culvert, Government Channel & retaining wall) and if the leased portion of the land required for the Government for the benefit of some other large general public schemes, the applicant should not object to handover the land to this department for which applicant is not entitled for any compensation and as well as legal entity. Further, the leased portion land has to be handed over to this department as is in original condition. The above proposed RCC Culvert will be the Government WRD property after the construction.
12. The Abutment, Wing wall, Return wall, etc., for the above proposed Culvert should be constructed well within the applicant's land on either side. The proposed RCC Culverts should be monitored and maintained for frequent inspection by the

Handwritten signature
16/12/25

applicants at their own cost. During Monsoon periods, the applicant should remove and clear the jungle & weeds, floating materials etc in the Government Channel at the bridge site at their own cost. The applicant should not damage the Government property and cause any inconvenience to common public.

13. In case of transfer of the above said lands to the third party / association in future, in such case the lease rent should be paid by the third party / association periodically without fail, otherwise the NOC will be revoked and constructed Culvert also removed without any correspondence, for which applicant is not entitled for any compensation and as well as legal entity.

14. The permission granted to the applicant, should not be altered / modified / changed to any others. Based on the records submitted by the applicants, the permission is granted. If any documents seem to be fake / manipulated / fabricated, in future the above permission will be cancelled without any correspondence and deposited amount for caution deposit, lease rent etc., will not be refunded. Hence, the applicant is solely responsible of genuinity of the documents submitted.

15. The applicant should do proper soil test, and suitable foundation should be selected depending upon the soil condition. The bottom portion of the bridge should be provided by Concreting at bed level at their cost so as to protect the erosion in future.

16. The WRD., will not be held responsible for the Structural Stability, safety and soundness of the Culvert proposed by the applicant and WRD specifically recommend only for construction of Culvert. The applicant should construct the proposed RCC Culvert at their own cost. The applicant is solely responsible for the structural safety and stability of the proposed RCC Culvert and at any cost, WRD will not be held responsible for design and drawing adopted for proposed construction of RCC Culvert.

17. The WRD officers should be allowed to inspect the site at any time during execution and thereafter, if necessary. Advance intimation should be given to the concerned WRD officers before commencement of work. WRD is giving opinion only in connection with the permission for construction of Culvert aspect and does not deliver any rights to the applicant to encroach the WRD / Government Lands.

18. The applicant should abide by the rules and regulation of the WRD from time to time. The applicant should also abide court of law & act of both State & Central Government from time to time.

19. The applicant should not object at any time for the maintenance work / improvements work of the channel / tank to be carried out by WRD. The applicant should give an undertaking in writing to the effect that the above proposal will not

Handwritten signature
16/12/25

obstruct in case any maintenance / improvement / development works as per Revenue records [FMB] which are to be carried out by WRD in future periodically.

20. The applicant should maintain the channel area as is in condition of Environmental, Ecology, and Naturalist and without encroachments & pollution etc., and should not deviate the Hydraulic particulars of the channel.

21. All safety measures should be taken without fail. Adequate arrangement for the safety of traffic by way of flagman, barricades, caution boards, danger lights (Day & Night) etc., as required should to be provided. The applicant should engage proper watch and ward so as to avoid any untoward incident upto completion of work.

22. The applicant should not carry out any other cross masonry structures across the channel without prior permission from WRD. The applicant should provide a pucca concrete bed in the channel at the proposed culvert sites without fail. The Culvert should be completed without any damage to the Government property or the damage caused during execution if any will be rectified fully by the applicant's cost.

23. The applicant's land should be filled with earth with proper compaction to the minimum level of (+)20.650 m to protect the site from inundation during floods. The process of earth filling and compaction should be done in layers of not more than 0.30 m depth to achieve the required degree of compaction for a depth varying from 2.140 m to 2.500 m depending upon the existing field levels and the existing applicant land should be raised to a minimum level of (+) 20.650 m (ie., (+) 2.090 above the Sill Level of Sluice No.5 of Chembarambakkam Tank which is (+)18.560 m). The all-round entire pavement level within the site should not be less than (+) 20.650 m. The applicant is suggested to have regular habilitation not below the MFL, since the existing field levels are below MFL.

24. The applicant should not object the common public for using the Culvert at any time and any cost.

25. During Monsoon periods, the applicant should remove and clear the jungle & weeds, floating materials etc in the Government Channel at the bridge site at their own cost. The applicant should not damage the Government property and cause any inconvenience to common public.

TECHNICAL SUGGESTIONS:

a. The applicant should prepare the development proposal by considering the suitable internal storm water drainage network as micro drain of suitable sizes within the site as per site condition and the same should be connected to the local drain/channel, rainwater harvesting, roads with road side drains sewerage treatment plant and its disposal and garbages / debris and other solid waste management as per norms in

J. Jayaram 16/12/25

existence within the applicant's land according to existing rules in force and should get proper approval from competent authority without fail.

The sewage or any unhygienic drainage (Treated or Untreated) should not be let into drain /channel/course at any cost and the debris and other materials should not be dumped into the drain /surplus course obstructing free flow of water. The applicants should make drainage network, at their own cost and the same is to be connected to natural storm water drainage/channel. There should not be any hindrance to the free flow of internal drain to downstream.

b. The applicants' lands are seems to be Ryotwari land which would be classified as Dry lands. Hence, these lands are to be converted into other zone from the agricultural zone by the competent authority. The applicants should get clearance certificate for this site from the Revenue department to make sure that the site is not an encroached property from the water body as well as confirming this proposed site boundaries.

c. Since the site exists abutting Channel in S.F.No.158, the necessary setback distance should be provided within the site as per the norms in existence and as per the rules in force of CMDA (as per the circular issued by the office of the Commissioner of Town & Country Planning, Chennai – 2 vide Roc.No.4367 / 2019-BA2 / 13.03.2019) during development. The CMDA should issue completion certificate only after obtaining compliance certificate NOC from WRD.

d. The sewage water from the applicants' land should not let into the drains and for the disposal of the sewage water and suitable arrangements should be made for the same by the applicant and as well as the construction materials/debris/garbage should not be dumped into the channel / river at any cost.

At any cost, sewage/sullage should not be let into channel, and the garbage, debris and construction materials should not be dumped into the channel/river restricting the free flow of water.

e. The necessary setback distance should be provided within the site as per site conditions along the channel as per the norms in existence and as per the rules in force of CMDA (circular issued by the office of the Commissioner of Town & Country Planning, Chennai – 2 vide Roc.No.4367 / 2019-BA2 / 13.03.2019) during development and there should not be any construction activity in setback area in future also. Moreover, the applicant should provide adequate passage along the channel course as per norms which are found necessary for accessing purpose of the heavy machinery for maintenance work / improvements work of the channel which are proposed to be carried out by WRD.

Handwritten signature and date: 16/12/25

The owner of the document received from the applicant in respect to the ownership is purely of applicant's responsibility and it is only for reference purpose to this department. The legal validity of this document should be verified by the Development / Revenue authorities. The specific remarks on inundation are purely issued on technical grounds in respect to the physical location of land.

Failing to comply with any of the above conditions, WRD reserves rights to withdraw the Technical opinion with NOC on Inundation point of view along with permission for construction of Culvert to the above proposed site and in event the applicant shall not be eligible for any compensation whatsoever and as well as legal entity.

J. Jay 16/12/25
for Chief Engineer, WRD.,
Chennai Region, Chennai-5.

Indu. G
16/12/25